

# SS-900



**Solar Panel: 3 × 460W, Mono**  
**GEL Battery: 6 × 200Ah, DC12V, 14400W·h**  
**Lamp: 4 × 150W LED, IP65, 90000Lms**  
**Tilt: 90° Electric**  
**Controller: 60A MPPT, 95% Efficiency**  
**Mast: Steel Q235, Square Telescopic type, 6.5 m, 5**  
**Sections,**  
**Manual Winch/Electric Winch/ Hydraulic,**  
**Lifting, 70kg Load, 117kph Windproof**  
**Trailer: US Standard, Ball Hitch, Single Axle, Manual**  
**Outrigger**  
**Charging Time: 8.8 hours**  
**Running Time: 19.2 hours**

